

State of Kansas



FORM - CP-8
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1964

CONSERVATION DIVISION
Wichita, Kansas

11-12-64

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rock Island Oil & Refining Company

Complete Address: 321 West Douglas, Wichita, Kansas

Lease Name: Fisher Well No. # 3

Location: SW NW SE Sec. 26 Twp. 25 Rge. 13(E) (W) W

County Stafford Total Depth 4300 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

255' of 8 5/8" surface pipe, cemented with 275 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,
Archie Elving