

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 22 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

March 15, 1963.

3-22-63

Dear Sir:

Mr. Doug Payne of Kent Well Service has this
 date requested permission to plug the following described well:

Mr. Doug Payne guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 813 First Nat'l Bnk Bldg. Wichita, Kansas.

Lease Name: Bowker "B" #1 Well No. #1

Location: SW-SE-NE Sec. 1 Twp. 25 Rge. 14 (E) (W) X

County Stafford Total Depth 4213 Abandoned
Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Doug Payne was instructed to plug the well as follows:

4157' of 4 1/2" long string Top perforation at 4046' Sanded to
4030' & 3 sacks cement. 226' of surface pipe circulated with
cement. Hole filled to 200' with mud, 10' rock bridge & 25
sacks cement. Hole filled to 40' with mud, 10' rock bridge
and 10 sacks cement to base of cellar.

Very truly yours,

Herbert J. Austin
 Conservation Division Agent