

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1971

CONSERVATION DIVISION
Wichita, Kansas

3-30-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Courange of Garvey Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Courange guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 300 W. Douglas Wichita, Ks

Lease Name: Waters I Well No. 1

Location: NW/NW/SE Sec. 3 Twp. 25S Rge. 14 (E) (W) X

County: Stafford Total Depth 3720 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Courange was instructed to plug the well as follows:

250 ft of 8 5/8 surface pipe cemented with 275 sacks. 1st

plug at 600 ft with 40 sacks cement. 2nd plug at 240 ft,

1/2 sack hulls, 25 sacks cement. Mud to 40 ft, plug, 1/2 sack

hulls, 10 sacks cement to surface. 5 sacks cement in rat

hole, 5 sacks cement in mouse hole. Globe Cementing Co.

Great Bend, Ks

Very truly yours,

H. Russell Bihirstein
Conservation Division Agent