

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1966

CONSERVATION DIVISION
Wichita, Kansas

10-14-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of B & B Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Newman's Inc.

Complete Address: 700 Petroleum Club Bldg., Tulsa, Oklahoma

Lease Name: Wilson Well No. # 1

Location: NE NE NW Sec. 5 Twp. 25 Rge. 14 (E)(W) W

County Stafford Total Depth 4395' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

276' of 8 5/8" surface pipe, cemented with 230 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent