



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1964

5-25-64

CONSERVATION DIVISION  
Wichita, Kansas

15-151-19125-0000

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Howard Roberts of Strata Drilling Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Strata Drilling Inc.

Complete Address: P. O. Box 355, Great Bend, Kansas

Lease Name: Tatlock Well No. # 1

Location: NE NW SE Sec. 27 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4468 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

328' of 10 3/4" surface pipe, cemented with 350 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with hulls, and cement with 35 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 15 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent