



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

19 - November 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-647-20303-0000

Dear Sir:

Mr. Albert Urruch of Kelso Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: Halliburton Oil Production Co.

Complete Address: Box 10 Stafford Kansas 67578

Lease Name: English Well No. 1

Location: E-SE-NW Sec. 1 Twp. 26S Rge. 16W (E) (W)

County: Edwards Total Depth: 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: This well had produced oil & then later prod. gas.

Mr. Urruch was instructed to plug the well as follows:

There is 454' of 8 1/8" surface casing cement circulated with 250 lbs of cement.

There is 4447' of 4 1/2" production ^{pipe} cemented with 100 lbs of cement. There is a

2 stag collar at 2360' cemented with 350 lbs of cement. The pipe was cemented

to 1990'. The perforations were from 2203' to 2207'. 1st plug ^{sanded} cement

off bottom back to 2150' with 4 lbs of cement. 2nd plug pumped 3 lbs

of hull + 25 lbs of jell released rubber plug and pumped 150 lbs of cement

on top of it to bring cement to 0'. Cement used 50/50 pump 4 1/2 gal 3 to C.C.

There was 1925' of 4 1/2" production pipe recovered. Plugging accomplished by Halliburton Co. out of ^{Very truly yours,} state

shut in pressure 250 lbs.

Paul Luthi
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1981
11-24-81

CONSERVATION DIVISION
Wichita, Kansas