

1 030415

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,156-0000

NE SW SW, SEC. 18, T 25 S, R 13 W/E
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Kachelman Well # 1-18

Operator: Texas Energies, Inc.

County Stafford #12, 35

Name & Address P. O. Box 947

Well Total Depth 4380 (Arbuckle let)

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address Box 329, Pratt, KS 67124

Company to plug at: Hour: 8:00 pm Day: 13 Month: April Year: 19 85

Plugging proposal received from Tony Earnst

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 850'

1st plug at 870' with 50 sx cement

2nd plug at 420' with 40 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plug water well

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 pm Day: 13 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement, 2nd plug at 420' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement and plugged water well

from bottom to top with cement.

RECEIVED STATE CORPORATION COMMISSION

5-21-85 MAY 21 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan (if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED (not) observe this plugging.

DATE 5-21-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 8228