

To: 1 041217  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-22,855-0000  
100' E & 50' N of  
SE SW NW, SEC. 18, T 25 S, R 13 W/EX

10-25

2260 feet from N&S section line

1090 feet from W&E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name Fisher Well # I-18

Operator: Globe Operating, Inc.

County Stafford 141.79

Name & Address P.O. Box 12

Well Total Depth 4363 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 25 Month: 10 Year: 19 96

Plugging proposal received from Ralph

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

was: 5 1/2" at 4362.76' w/160 sx cement. Perfs at 4044-50, 4224-42'

1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 25 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

10-30-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (and \_\_\_\_\_) observe this plugging.

DATE 10-31-96

Signed Steve Pfeifer (TECHNICIAN)

INV. NO. 46893

10-25