

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20205-00-00  
Spot: NW SW NE Sec/Twnshp/Rge: 18-25S-13W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: CURTIS Well Number: 3  
County: STAFFORD Total Vertical Depth: 4220 feet

Operator License No.: 3942  
Operator Name: BIG "O"  
Address: 2820 PASEO DRIVE  
GREAT BEND, KS 67530

11/2

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 292 WITH 285 SX CMT  
Production: Size 5.5 feet: 4219 WITH 125 SX CMT  
Liner: Size feet: 137.15

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/02/2000 11:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: BRIAN FRENZEL Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 125 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/02/2000 12:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:  
PERFS AT 4080-4086'. SAND TO 4030' & 5 SX CMT. PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 125 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 800#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2" CASING.

Plugged through: CSG

11-6-00

District: 01

RECEIVED  
STATE CORPORATION COMMISSION

Signed Richard M. Lacey  
(TECHNICIAN)

NOV 6 2000  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 11/7/00 NOV 03 2000  
INV. NO. 2001060942 MP

Form 13