

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20191-00-00
Spot: NW NW NE Sec/Twnshp/Rge: 18-25S-13W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: CURTIS Well Number: 1
County: STAFFORD Total Vertical Depth: 4316 feet

Operator License No.: 3942
Operator Name: BIG "O"
Address: 2820 PASEO DRIVE
GREAT BEND, KS 67530

11/2

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 281 WITH 282 SX CMT
Production: Size 5.5 feet: 4315 WITH 150 SX CMT
Liner: Size feet: 140.27

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/02/2000 12:45 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN FRENZEL Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 125 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/02/2000 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 4048-4100'. SANDED TO 4000' AND 5 SX CMT WITH BAILER. PUMPED CMT DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - & 125 SX CMT. MAXIMUM PRESSURE 750#. SHUT IN WITH 750#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2' CASING.

Plugged through: CSG

District: 01

11-6-00
RECEIVED
STATE CORPORATION COMMISSION
NOV 6 2000
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard M. Lacey
(TECHNICIAN)
INVOICED
DATE 11/7/00 NOV 03 2000
INV. NO. 20001060942 MP

Form SP-3