

1 120164

11-15

API NUMBER: 15- 185-21,417-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NW, SEC. 36, T 25 S, R 13 W/E

2970 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5533

Lease Name Harrison Well # 1

Operator: Arrowhead Petroleum Inc.

County Stafford 140.69

Name & Address 400 North Woodlawn, Suite 29

Well Total Depth 4329 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 15 Month: 11 Year: 19 88

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4305' Perfs at 4132-36' Junk in hole past 4200'

1st plug sand back to 4080' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1988 11-23-88

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 15 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4080' and dumped 4 sx cement on top of sand with bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2815' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
DEC 1 1988

did not observe this plugging.

Signed Ocean Rankin (TECHNICIAN)

DATE

INV. NO. 22201