

R

1 080310

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 3-2-59

C E/2 SE NW, SEC. 29, T 25 S, R 13

3300 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

Lease Name Leiss Well # 3

Operator: K & E Drilling, Inc.

County Stafford 141.90

Name & Address 100 South Main, Suite 300

Well Total Depth 4366 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 16 Month: January Year: 19 85

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4364' PBTD 4328' Perfs 4277-88'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls  
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:45 pm Day: 16 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top  
of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,  
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx  
cement.

RECEIVED STATE CORPORATION COMMISSION

1-23-85

JAN 23 1985

Maximum pressure 200 psi and shut in 0

Remarks: Recovered 3000' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-28-85 I (did not) observe this plugging.

INV. NO. 6687

Signed J. A. Metz (TECHNICIAN) S-ao