

1080311

R

(W)

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 6-20-55
NW SE NW , SEC. 29 , T 25 S, R 13

3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

Lease Name Leiss Well # 1

Operator: K & E Drilling, Inc.
Name & Address: 100 South Main, Suite 300
Wichita, KS 67202

County Stafford 141.02

Well Total Depth 4339 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 16 Month: January Year: 1985

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4338' PBD 4299 Perfs at 4269-74, 4263-65, 3857-61

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

Rec. 3327'-5 1/2"

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 pm Day: 16 Month: January Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 3800' and dump 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

1-23-85

JAN 23 1985

Maximum pressure 500 psi and shut in 100 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 3300' 5 1/2" casing
(if additional description is necessary, use BACK of this form.)

(If applicable, observe this plugging.)

INVOICED

DATE 1-28-85

Signed J. H. Metz (TECHNICIAN)

INV. NO. 6685