

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-11449-00-01
Spot: CSESENE Sec/Twnshp/Rge: 30-25S-13W
2970 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: MCCANDLESS SWD Well Number: 1
County: STAFFORD Total Vertical Depth: 4732 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1140 WITH 500 SX CMT.
Production: Size 4.5 feet: 4437 WITH 225 SX CMT.
Liner: Size feet: 153.79

Well Type: SWD UIC Docket No: D08223.0 Date/Time to Plug: 01/24/2001 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT DOWN TUBING @ 3968'. 1ST PLUG AT 1180' WITH 50 SX CMT. 2ND PLUG AT 850' WITH 25 SX CMT. 3RD PLUG AT 300' WITH 25 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 02/01/2001 3:30 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4437'. PERFS AT 4319-4334'. ANHYDRITE @ 832'. HOLES IN CASING BELOW 1800' TO 2300'. ON 01/24/01 PUMPED DOWN TUBING AT 3968' WITH 200# HULLS & 50 SX COMMON CMT. PULLED TUBING. ON 02/01/01 TAGGED BOTTOM PLUG CMT WITH SLICK LINE AT 3584'. PULLED CASING TO 1180' AND PUMPED 200# HULLS - 20 SX GEL - 50 SX CMT. PULLED TO 850' PUMP 25 SX CMT. PULLED TO 300' PUMP 25 SX CMT. PULLED TO 40' PUMP 20 SX CMT. SURFACE PIPE HEAD 15' BELOW G.L. GOOD CIRCULATION THROUGHOUT JOB.

INVOICED

DATE 03-07-2001

INVOICE NO. 2001061435

RECEIVED
STATE CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1527' OF 4 1/2" CASING.

Plugged through: CSG

FEB 14 2001
2-14-01
CONSERVATION DIVISION
WICHITA, KANSAS

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

FEB 02 2001

[Signature]
Form CP-273