

1 030.146

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 11-11-58
C W/2 NW NE, SEC. 30, T 25 S, R 13 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

_____ feet from N/S section line

_____ feet from W/E section line

Operator: K & E Drilling
Name & Address 100 South Main, Suite 300,
Wichita, KS 67202

Lease Name J.C. McCandles Well # 'B' 2

County Stafford

Well Total Depth 4335 140.89 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 312

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 3 Month: April Year: 19 84

Plugging proposal received from James Ray

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2 set at 4331.5 PBDT 4318 Perfs 3859 - 64 3976 - 80 3876 - 81 3892-3900.

1st plug sand back to 3800 and dump 5 sx cement on top of sand

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release plug and pump additional 150 sx cement

Maximum pressure 500# and shut-in pressure 200#

Plugging Proposal Received by Steve Demont (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 3 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4331.5 PBDT 4318 Perfs 3859-64 3876-81 3892-3900 3976-80

1st plug sand back to 3800' and dump 5 sx cement on top of sand

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release plug and pump additional 150 sx cement

Maximum pressure 500# and shut-in pressure 200#

Remarks: Use 60/40 Pozmis 2% gel 3% cc by Sun. They recovered 2945 of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 4-9-84

APR 06 1984

Signed Steve Demont (TECHNICIAN)

INV. NO. 1095 4-3

CONSERVATION DIVISION Wichita, Kansas

4-6-84