

15-185-00501-0000

10-4

To: 1 120838  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 1958  
SE SE NE, SEC. 1, T 25 S, R 14

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238  
Operator: Petroleum, Inc.  
Name:  
Address 301 N. Main, Ste. 900  
Wichita, KS 67202

2970 feet from S section line  
330 feet from E section line

Lease Name Seewers Unit Well # 6-1  
County Stafford  
Well Total Depth 4337 140.95 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kincaid Well Service License Number 7252

Address P.O. Box 276, Ellinwood, KS 67526

Company to plug at: Hour: 12:30 p.m. Day: 21 Month: 9 Year: 19 93

Plugging proposal received from Terry Naylor

(company name) Petroleum Inc. (phone) 316-793-8471

Work: 5 1/2" at 4334' w/225 sx cement, PBD 4000', Perfs at 3828-32, 3839-46'  
Top of tubing fish at 2700'

Pump in 5 1/2" casing with 2 sx hulls, 50 sx cement, 26 sx gel, and 125 sx cement.  
Pump down 5 1/2" X 8.5/8" annulus with 150 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 4 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 9/21/93-Unable to plug according to proposal because of hole in 5 1/2" casing at 450'. 9/28/93-Ran tubing to 2688' and pumped 50 sx cement, pulled tubing to 906' and pumped in 320 sx cement. Cement didn't circulate. Ran line-top of cement at 390'.  
4/10/93-Filled 5 1/2" casing with 40 sx cement and pumped in 8 5/8" X 5 1/2" annulus with 80 sx cement.  
5 1/2" casing perforated at 850'-base of Anhydrite.  
Pumping pressure 0-200 psi and shut in 0 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
10-11-93  
OCT 11 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED  
DATE 10-13-93  
INV. NO. 38943

Signed [Signature] (TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas