

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-19002-00-01  
Spot: NWENW Sec/Twnshp/Rge: 1-25S-14W  
330 feet from N Section Line, 1650 feet from W Section Line  
Lease/Unit Name: SANDER Well Number: 2  
County: STAFFORD Total Vertical Depth: 4304 feet

Operator License No.: 4184  
Operator Name: CASINO PETROLEUM CO.  
Address: PO BOX 415  
ELLINWOOD, KS 67526

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 317  
Production: Size 5.5 feet: 4136 139.88  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2000 3:00:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/27/2000 5:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 4012-20, 4039-49. SAND TO 3950' AND 5 SX CMT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 800' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 2000  
10-11-00

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

INVOICE Signed Richard W. Lacey  
(TECHNICIAN)  
DATE 10/13/00  
INV. NO. 2001064815  
OCT 03 2000

Form C 

MP