

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19003-00-00
Spot: CSWNW Sec/Twnshp/Rge: 1-25S-14W
1980 feet from N Section Line, 660 feet from W Section Line
Lease/Unit Name: SANDER Well Number: 4
County: STAFFORD Total Vertical Depth: 4302 feet

Operator License No.: 4184
Operator Name: CASINO PETROLEUM CO.
Address: PO BOX 415
ELLINWOOD, KS 67526

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 307
Production: Size 5.5 feet: 4344
Liner: Size feet: 139.82

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/02/2000 2:00:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: 1ST PLUG AT 800' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/02/2000 4:03 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:
PERFS AT 4002-4006, 4021-27, 4031-35, 4080-85. SAND TO 3950' & 4 SX CMT. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

10-11-00
RECEIVED
STATE CORPORATION COMMISSION
OCT 11 2000

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 5 1/2" CASING.

Plugged through: CSG

CONSERVATION DIVISION
Wichita, Kansas

District: 01

Signed Richard W. Lacey (TECHNICIAN)

INVOICED
DATE 10/13/00
INV. NO. 2001060815

OCT 06 2000

Form 2/3

MP