

1 080452

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
230'N & 130'W OF
C SW SW , SEC. 2 , T 25 S, R 14 W/4

890 feet from S section line
4750 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6166

Lease Name Easterly Well # 1

Operator: Bill Chew, Inc.

County Stafford 142.09

Name & Address P. O. Box 90,
Lyons, KS 67554

Well Total Depth 4372 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 26 Month: November Year: 19 85

Plugging proposal received from Norman Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4372' Perfs at 3702-3706

1st plug pump 30 sx cement to bottom and stop plug at 3600'

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 pm Day: 26 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 35 sx cement and stopped plug at 3600',

2nd plug squeezed well with 3 sx hulls, 10 sx gel,, 50 sx cement, 10 sx gel, 1 sack hulls,
released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 200 psi.

Remarks: Recovered 2600' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 12-6-85

DEC 5 1985 Signed

J. H. [Signature]
(TECHNICIAN)

INV. NO. 1128K

12-5-85

CONSERVATION DIVISION
Wichita, Kansas