

To: 1 030686  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,105-0000  
NE NE SW, SEC. 2, T 25 S, R 14 W/E  
2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5992  
Operator: Patton Oil Company  
Name & Address: 672 West 4th Street  
Hoisington, KS 67544

Lease Name Curtis Well # 1  
County Stafford 135.95  
Well Total Depth 4183 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_  
Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 4 Month: April Year: 19 86

Plugging proposal received from Roger Lust  
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4180' PBTD 3890' Perfs (top) at 3804'  
1st plug sand back to 3750' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, :  
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 am Day: 4 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3750' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10  
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 400 psi

Remarks: Recovered 2614' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE APR 15 1986

INV. NO. 13454

APR 15 1986

CONSERVATION DIVISION

Signed Steve Krumont  
(TECHNICIAN)

4-15-86