

To: 1-21090  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. **PLUGGING SECTION**  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-21106-0001  
SE SE SW, SEC. 2, T. 25 S, R. 14 W/E  
330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9449  
Operator: Great Eastern Energy  
Name & Address 5990 Greenwood Plaza Blvd. #116  
Englewood, CO 80111

Lease Name Curtis Well # 2  
County Stafford 134.19  
Well Total Depth 4129 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 8 Month: 12 Year: 1995

Plugging proposal received from Bill Reed  
(company name) Great Eastern Energy (phone) 316-653-2277

Notes: 4 1/2" at 4128' w/150 sx cement, PBSD 3820', Perfs at 3796-3804'  
1st plug sand back to 3746' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released  
8 5/8" wiper plug and pump 100 sx cement.

RECEIVED  
DEC 20 1995  
12-20-95

Plugging Proposal Received by Duane Rankin CONSERVATION DIVISION  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 8 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 3746' and dumped 4 sx cement on top of sand  
through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 1-5-96

INV. NO. 44391

Signed Duane Rankin  
(TECHNICIAN)