

1 030248

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,060-0000

NW SW SE , SEC. 5 , T 25 S, R 14 W ~~XX~~
990 feet from ~~XX~~ SE Corner of section line
2310 feet from ~~XX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Neill Well # 1

Operator: Falcon Exploration, Inc.

County Stafford

Name & Address Suite 1531, KSB Building

Well Total Depth 4411 143.36 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cougar Drilling, Inc. License Number 5138

Address 555 North Woodlawn, Suite 114, Wichita, KS 67208

Company to plug at: Hour: 5:00 am Day: 12 Month: August Year: 19 84

Plugging proposal received from Gary Bagby

(company name) Cougar (phone) 316-685-7677

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 930' with 50 sx cement

2nd plug at 390' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Skumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:00 am Day: 12 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 930' with 50 sx cement, 2nd plug at 390' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

8-16-84

AUG 16 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

Signed Steve Skumant
(TECHNICIAN)

DATE 8-17-84

INV. NO. 3192 8-12 OCT 0-2 1984