

1080241

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-20,676-0000

SW NE SE , SEC. 30 , T 26 S, R 15 W/E  
N SE Corner of  
1650 feet from ~~XXX~~ section line  
W SE Corner of  
990 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Tatlock Well # 1

Operator: Texas Energies, Inc.

County Pratt

Name & Address P. O. Box 947

Well Total Depth 4660 <sup>45</sup> feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 456

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 23 Month: October Year: 19 84

Plugging proposal received from Joe Maize

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4595' PBD 4595' Perfs at 4414-17'

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00 noon Day: 23 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4595' PBD 4595' Perfs at 4414-17'

1st plug sanded back to 4350' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Maximum pressure 100 psi and shut in pressure 0.

RECEIVED  
STATE CORPORATION COMMISSION  
10-31-84  
OCT 31 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

(did observer this plugging.)

Signed J. H. Metz S.D.  
(TECHNICIAN)

INVOICED  
DATE 11-7-84  
INV. NO. 4692