

5-20-88

1 040100

API NUMBER 15-047-2179-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NW, SEC. 1, T 26 S, R 16 W/E
3140 feet from S section line
4260 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3454
Operator: Little Guy Oil & Gas Inc.
Name & Address: P.O. Box 8561
Pratt, KS 67124

Lease Name R.G. Fouse Well # 4
County Edwards 148.59
Well Total Depth 4572 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 20 Month: 5 Year: 1988

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4571' Perfs at 4344-64'

1st plug sand back to 4290' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 20 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4258' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 450 psi and shut in 150 psi.

RECEIVED STATE CORPORATION COMMISSION

5-24-88 MAY 24 1988

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3700' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 5-25-88
INV. NO. 20874

Signed Stephen J. Pfeifer (TECHNICIAN)