

To: 1 030981  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-21  
API NUMBER 15-047-21,163 -0000  
SW SW NW, SEC. 1, T 26 S, R 16 W  
2970 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3454

Operator: Little Guy Oil & Gas, Inc.  
Name & Address: P.O. Box 8561  
Pratt, KS 67124

Lease Name R.G. Fouse Well # 2  
County Edwards 149.73  
Well Total Depth 4607 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated  Wichita, Kansas 9-27-88

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:25 a.m. Day: 21 Month: 9 Year: 1988

Plugging proposal received from Ken Gates

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4590' PBTD-4030' CIBP Top perfs at 2991-95' (4 sets)

1st plug sand back to 3940' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:50 a.m. Day: 21 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 3940' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1476' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 10-6-88

Signed Steve Durrant (TECHNICIAN)

INV. NO. 22526