

1 030980

9-21

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-21,148-0000

NW SW SW, SEC. 1, T 26 S, R 16 WEX

710 feet from S section line

4935 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3454

Lease Name R.G. Fouse Well # 1

Operator: Little Guy Oil & Gas, Inc.

County Edwards 150.35

Name &

Address P.O. Box 8561

Well Total Depth 4626 feet

Pratt, KS 67124

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1988

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well  Gas Well  Lost Well  SWD Well  D&A

Other well as hereinafter indicated 9-27-88

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:20 p.m. Day: 21 Month: 9 Year: 19 88

Plugging proposal received from Ken Gates

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4600' Perfs at 4372-87'

1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:10 p.m. Day: 21 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-6-88

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 22524