

9-21

To: 1 030979
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,191-0060

TECHNICIAN'S PLUGGING REPORT

C S/2 SW SW, SEC. 1, T 26 S, R 16 W/4E
330 feet from S section line
4620 feet from E section line

Operator License # 3454

Lease Name R.G. Fouse Well # 5

Operator Name: Little Guy Oil & Gas Inc.

County Edwards 146.90

Address P.O. Box 8561

Well Total Depth 4520 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 427

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:25 a.m. Day: 21 Month: 9 Year: 19 88

Plugging proposal received from Ken Gates

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4520' Perfs at 4348-62'

1st plug sand back to 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:50 a.m. Day: 21 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 50' above perfs and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2303' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (could not observe this plugging.)

DATE 10-6-88

Signed Steve Pfeifer (TECHNICIAN)

INV. NO. 22525