

To: 1-120395
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,557-0000

NW, SEC. 2, T. 26 S, R. 16 W/R

odd Section 200 feet from S section line
1330 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Cudney "A" Well # 2

Operator: Oil Producers Inc. of Kansas

County Edwards 143.13

Name & Address Box 8647

Well Total Depth 4404 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 2 Month: 4 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4385' w/150 sx cement Perfs at 3964-69'

1st plug sand 4 1/2" casing back to 3914' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:10 a.m. Day: 2 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3914' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2540' of 4 1/2" casing.

(If additional description necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this work. 4-6-90

DATE 4-17-90

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 27862

CONSERVATION DIVISION
Wichita, Kansas