

To: 1 060729
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

486-0001
API NUMBER 15-047-20, #25
E-SW-SW, SEC. 2, T 26S, R 16 W10
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061 Lease Name Bryant Well # B-1
Operator: Oil Producers of Kansas County Edward 144.30
Name & Address 1346 N. Woodlawn Box 8647
Wichita Kansas 67208
Well Total Depth 4440 feet
Production Conductor Pipe: Size 4 1/2" feet 4439
Surface Casing: Size 8 5/8" feet 442

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Perforations 4418' to 32'

Plugging Contractor Great Bend Casing Pulling Co. License Number 4635

Address Box 768, Great Bend, Kansas 67530

Company to plug at: Hour: 1:00 PM, Day: 20 Month: November Year: 1985

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pulling Co. (phone) 316-793-9721

were: 1st plug sand back to 4360' dump 4 bbls cement through bailor. 2nd plug squeeze well down 8 5/8" w/ 3 bbls hulls & 15 bbls gell & 50 bbls cement & 10 bbls gell & 1 bbl hulls & release wood plug & pump 120 bbls cement.

Plugging Proposal Received by Paul A. Luthin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:40 PM Day: 20 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug sand back to 4360' dump 4 bbls of cement on top of sand through bailor. 2nd plug squeeze through 8 5/8" w/ 3 bbls hulls & 15 bbls gell & 50 bbls cement & 10 bbls gell & 1 bbl hulls & released wood plug & pumped 120 bbls cement. Max pressure w/ 300# shut in @ 0# pressure. Allied pumped 60/40 foam mix w/ 6 1/2" gell.

Remarks: They recovered 2500' of 4 1/2" production casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 11 1985

DEC 2 1985

Signed Paul A. Luthin (TECHNICIAN)

INV. NO. 11449

JAN 15 1986 CONSERVATION DIVISION
Wichita Kansas

12-2-85