

To: 1 040679
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-4

API NUMBER 15-047-00075-0000 28 R
Drilled 11/5/58
NW SW NW, SEC. 2, T. 26 S, R. 16 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635

3630 feet from S section line

4950 feet from E section line

Lease Name Bryant Well # 1

Operator: Great Bend Casing Pullers Inc.

County Edwards 143.74

Name & Address P.O. Box 251

Well Total Depth 4423 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 415

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 4 Month: 8 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4418', PBDT 3970', Perfs at 3944-50'

1st plug sand back to 3890' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 4 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3890' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2198.55' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

8-13-92

INVOICED

(If used, ~~observe~~ observe this plugging.)

DATE 8-20-92

Signed Stephen Pfeifer
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 35996