

1080534

218 R

API NUMBER 15- 047-20,766-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C S/2 S/2 NE SEC. 2, T 26 S, R 16 W E

2970 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Wood Well # 3

Operator: A. L. Abercrombie, Inc.

County Edwards 156.00

Name & Address 801 Union Center,

Well Total Depth 4800 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 am Day: 27 Month: June Year: 19 86

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4540' PBD 4503' Perfs at 4356-60'

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 am Day: 27 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of

sand. 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 100 psi and shut in 0

Remarks: Recovered 3000' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ Titan (If additional description is necessary, use BACK of this form.)

INVOICED  
DATE JUL 10 1986  
INV. NO. 14307

STATE CORPORATION COMMISSION  
JUL - 8 1986  
Conservation Division  
Signed J. H. Metz (TECHNICIAN)

7-8-86