

1 090017

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-17
API NUMBER 15- 047-21, ⁹⁶046 - 0000

SW SW NW, SEC. 2, T 26 S, R 16 W/E

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Lease Name Dick Snow Well # 1

Operator: CMX Inc.

County Edwards 147.12

Name & Address 1026 Union Center

Well Total Depth 4527 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 10 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4523' w/150 sx cement, PBD 4500'. Perfs at 4440-46'

1st plug sand back to 4390' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 140 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 17 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4390' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 140 sx cement.

Maximum pressure 350 psi and shut in 350 psi.

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1990
10-19-90

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2300 CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.)

INVOICED (VOID) observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE 10-26-90

INV. NO. 29746

SUNWEST EXPLORATION COMPANY
2851 S. PARKER RD., #1310
AURORA, CO 80014


#1 DICK SNOW
(BRYANT)

2-26-16W
SW SW NW

CONTR DAMAC DRILLING, INC. CTY EDWARDS

GEOL _____ FIELD WIL

ELV 2080 KB SPD 4/26/83 CARD ISSUED 9/1/83 IP P 15 BO & 15 BWPD
2072 GL KIND 4440-4446



LOG	Tops	Depth/Datum
HEEB		3761-1681
DOUG		3807-1727
BR LM		3912-1832
LKC		3925-1845
BKC		4212-2132
CHER SH		4373-2293
CHER SD		4375-2295
CONG		4413-2333
KIND SD		4438-2358
*VIOLA		4518-2438
RTD		4527-2447
LTD		4530-2450
*SAMPLE TOP		

API 15-047-21,096

8 5/8 " 455; 5 1/2 " ~~4876/250~~ SX **4523' / 150 SX**
NO DST'S
MICT - CO, PF (KIND) 4440-46; W/2 SPF, AC 500 GAL (7 1/2 %
MCA), FRAC W/10,000# SD & 18,000 GAL GEL, SWB DWN, TSTD
SO, POP, P 15 BO & 15 BWPD

INFO RELEASED: 2/16/84 - WAS OIL WELL - TIGHT HOLE
NOTE: 5/19/83 - ORIGINALLY FIRST REPORTED AS #1 BRYANT,
NW NW SW