

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -185-11291-0000 (of this well)

Operator's Full Name Ervin Schneider

Complete Address Box 86-Tribune, Ks. 67879

Lease Name Barr Well No. 1

Location C NE SE Sec. 9 Twp. 25S Rge. 11 (E) (W) X

County Stafford Total Depth 3930

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11 Am. Day 15 Month 12 Year 1979

The above well was plugged as follows:

253' 8 5/8" casing w/275 sax cement. 5 1/2" casing set at 3925' w/100
sax cement. Sand back to 3900'-Top sand w/ 5 sax mixed cement w/dump
bailer. Pull 2415' 5 1/2" casing. Sun Mixed & pumped 8 sax hulls 25 sax
gel-125 sax cement to top of casing. Shut in w/100# pressure. 12-17-79

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-18-79

INV. NO. 1106w

Signed: [Signature]
Well-Plugging Supervisor