

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1965

CONSERVATION DIVISION
Wichita, Kansas

3-1-65

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Robert L. Jones & R. D. Olson

Complete Address: 353 North Armour, Wichita, Kansas

Lease Name McCune Well No. # 1

Location C SW NW Sec. 10 Twp. 25 Rge. 11 (E) (W) W

County Stafford Total Depth 3550'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was washed down to 3550'

Plugging Contractor: Terrel Drilling & Production

Address: Box 606, Russell, Kansas License No.

Operation Completed: Hour 1:15 PM Day 27th Month Feb. Year 1965

The Above well was plugged as follows:

263' of 8 5/8" surface pipe, cement circulated. Fluid level in the hole
was at 103*. 1st cementing plug and 1/2 sack of hulls was pushed in fluid
to 240', and cemented with 25 sacks, through the drill pipe. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged solid with
hulls and dry cement on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 3/1/65
INV. NO. 734-14

Signed: Archie Elving
Well Plugging Supervisor

INVOICED