

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSIONMAR 12 1964
3-12-64
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name G. C. ZinkComplete Address: Turon, KansasLease Name Potter Well No. # 1Location NW NW SE Sec. 15 Twp. 25 Rge. 11 (E) (W) WCounty Stafford Total Depth 3924Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Glen & Smith Casing Pulling Co.Address: 204 E. Sixth, Ellinwood, Kansas License No. 396Operation Completed: Hour 12:30PM Day 11th Month March Year 1964

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cemented with 225 sacks. 3914' of 5 1/2" long
string, cemented with 125 sacks. Plug back to 3600'. Top perferation
3560'. Bottom of hole was sanded to 3550', and cemented with 5 sacks.
Fluid was up in the hole and would not bail down. Plug was pushed to
250', bridged with 10' of rock. 5 sacks of cement was mixed in barrel
and put on plug, through dump bailer, and let set over night. Next morn-
ing hole bailed down, and 20 sacks cement was added to plug. Hole was
filled with mud to 40', with 10' rock bridge, and cemented with 10 sacks
to base cellar. 3018' of 5 1/2" long string was recovered from the hole.
 I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/12/64
INV. NO. 8449-uSigned: Archie Elving
Well Plugging Supervisor