

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 20 1973  
CONSERVATION DIVISION  
Wichita, Kansas

2-20-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co

Complete Address 217 N Water Wichita, KS

Lease Name H. Reissig Well No. 1-V

Location SW/NW/NE Sec. 23 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4259

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 2:00 PM Day 19 Month 2 Year 1973

The above well was plugged as follows:  
323 ft 8 5/8 surface cemented with 260 sacks. 4248 ft 5 1/2 long string  
cemented with 150 sacks. Open hole. Sand to 4225 ft, 5 sacks cement  
with bailer. Pulled 3000 ft 5 1/2. Pump 2 sacks hulls, 15 sacks gel,  
100 sacks cement to surface.  
Pumped by Sun Cementing Co Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 2/22/73

INV. NO. 7001-W