

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 10 1964

CONSERVATION DIVISION  
Wichita, Kansas

11-10-64

Operator's Full Name William Cohen Company

Complete Address: Box 2421, Wichita, Kansas

Lease Name McCandless Well No. # 1

Location SE NW Sec. 23 Twp. 25 Rge. 13 (E) W

County Stafford Total Depth 4218

Abandoned Oil Well X Gas Well     Input Well     SWD Well     D & A    

Other well as hereafter indicated:    

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: 204 East Sixth St., Ellinwood, Kansas License No. 396

Operation Completed: Hour 1:00PM Day 9th Month Nov. Year 1964

The Above well was plugged as follows:  
247' of 8 5/8" surface pipe, cement circulated. 4216' of 5 1/2" long string, cemented with 75 sacks. Bottom of hole was sanded to 4200', and cemented with 5 sacks. I visited this location about noon on Sat. Nov. 7, they had their pipe loose, and had several joints laid down. I told them after they had their pipe laid down, they could possible expect Dakato Water to come up in the hole, and that they could set a bridge plug at the bottom of the surface pipe, and mix about 4 sacks of cement and put on plug, through dump bailer. Let set over-night, bail hole dry next morning. I told them to call me regardless. I received no call. Mon. Nov. 9. I revisited this location again, they had the bottom plug set at 240', and cemented with 30 sacks. They failed to call me and me not witnessing this plugging, all I have is their word, and according to the fill up in the hole, I have reasons to believe that these pluggers, Glen & Smith were not truthful with me. I told this to Glen & Smith, and they agreed that any time in the future that this well should give any plugging problems, that they would be fully responsible, and not reflect on the operator. I feel that Glen & Smith Casing Pulling Co., 204 E. 6th, Ellinwood, Ks., should be held fully responsible for the plugging of this well. 3489' of 5 1/2" long string recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 11/13/64

INV. NO. 154-W

Signed: Archie Elving

Well Plugging Supervisor