

CP-3

TC KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 2 1962

CONSERVATION DIVISION
Wichita, Kansas

8-2-62

Operator's Full Name Chief Drilling Co.

Complete Address: Box 787, Great Bend, Kas.

Lease Name Mc Candless Well No. 1

Location NE NW NW Sec. 23 Twp. 35 Rge. 13 (E) (W) ✓

County Stafford Total Depth 4250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A ✓

Other well as hereafter indicated: _____

Plugging Contractor: Co tools

Address: _____ License No. _____

Operation Completed: Hour 8:30pm Day 29 Month 7 Year 1962

The Above well was plugged as follows:

319' of 8 5/8" surface casing. Hole was
filled to 500' with heavy drilling mud. Cementing
plug set at 300' with 30' of 30' sand cement
grout through drill pipe. Hole grouted to
35'. Cementing plug set at 35' and cement
grout to base of casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/31/62
INV. NO. 5460-W

Signed: [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1962

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

McCANDLESS #1
NE NW NW Sec. 23-25S-13W
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 7-19-62
Completed: 7-29-62

D & A

Casing Record: 8-5/8" @ 219' w/200 sacks Sunset Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand, gravel & Red Bed	0	219	1920 Gr.
Red Bed & Sand	219	752	1922 D.F.
Anhydrite	752	769	1925 K.B.
Shale & Shells	769	1600	
Shale & Lime Streaks	1600	1750	
Shale	1750	1795	
Shale & Lime	1795	2100	
Lime	2100	2255	
Lime & Shale	2255	3250	
Lime	3250	3455	
Lime & Shale	3455	3580	
Lime	3580	4080	
Chert & Lime	4080	4210	
Cherty Lime & Sand	4210	4250	
T.D.	4250		

<u>FORMATION TOPS</u>	
Anhydrite	752 +1173
Heebner	3478 -1553
Toronto	3499 -1574
Douglas	3520 -1595
Brown Lime	3633 -1708
Lansing	3661 -1736
Base Kansas City	3932 -2007
Conglomerate	4040 -2115
Viola	4112 -2187
Simpson	4220 -2295
Total Depth	4250 -2325

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NW NW Sec. 23-25S-13W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 30th day of July, 1962.

Carmen Reinhardt Leiker
Carmen Reinhardt Leiker, Notary Public

My commission expires: Jan. 26, 1963.