

*R*

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1967

CONSERVATION DIVISION  
Wichita, Kansas

3-17-67

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued March 6, 1967.

Operator's Full Name Chief Drilling Company

Complete Address: Box 797, Great Bend, Kansas

Lease Name Kipp Well No. # 1

Location NW SE NE Sec. 20 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4370'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:30PM Day 16th Month March Year 1967

The Above well was plugged as follows:

301' of 8 5/8" surface pipe, cemented with 285 sacks. 4369' of 5 1/2" long  
string, cemented with 600 gallons of Latex. Plug back T.D. 4350'. Top  
perferation 4325'. Bottom of the hole was sanded to 4300', and cemented  
with 5 sacks, through the dump bailer. 3026' of 5 1/2" long string was  
recovered from the hole. A squeeze job was necessary. 10 sacks of Gel-  
Mud and 80 sacks of cement was pumped into the surface pipe, through a  
8 5/8" swage to a pressure of 450 pounds, bringing the top of the cement  
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 3-17-67

INV. NO. 4920-W