

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued March 6, 1967.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1967

3-17-67

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company

Complete Address: Box 797, Great Bend, Kansas

Lease Name Kipp Well No. # 2

Location SW SE NE Sec. 20 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4435'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:00AM Day 16th Month March Year 1967

The Above well was plugged as follows:

288' of 9 5/8" surface pipe, cemented with 285 sacks. 4390' of 7" long
string, cemented with 50 sacks of Posmix and 600 Gallons of Latex. Plug
back T.D. 4300'. Top perferation 4263'. Bottom of the hole was sandèd to
4250', and cemented with 7 sacks. 2143' of 7" long string was recovered from
the hole. A squeeze job was necessary. 10 sacks of Gel-Mud and 100 sacks of
cement was pumped into the surface pipe, through an 9 5/8" swage to a pressur
of 390 pounds, bringing the top of the cement to the base of the cellar.
This cementing was done by Knight Casing Pulling Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3-17-67

INV. NO. 4921-W