

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued May 26, 1967.

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1967
6-16-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company

Complete Address Box 797, Great Bend, Kansas 67530

Lease Name Kipp Well No. # 3

Location SE SW NE Sec. 20 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4442'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 5:15 PM Day 12th Month June Year 1967

The above well was plugged as follows:

290' of 10 3/4" surface pipe, cemented with 285 sacks. 4396' of 7" long string,
cemented with 166 sacks. Top perforation 4292'. Bottom of the hole was sanded
to 4200', and cemented with 7 sacks, through the dump bailer. 2100' of 7" long
string was recovered from the hole. Hole was squeezed. 10 sacks of Gel-Mud,
and 100 sacks of cement was pumped into a 10 3/4" swage, to a pressure of
300 lbs. Next day hole was filled with 4 sacks of cement to the base of the
cellar. This cement was pumped by Knight Casing Pulling Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6-16-67
INV. NO. 5410-W

Signed: Archie Elving
Well Plugging Supervisor