

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: 502 Ritz Bldg., Tulsa, Oklahoma

Lease Name: L. G. Simon Well No. # 1

Location: NE NE NW Sec. 33 Twp. 26 Rge. 11 (E)(W)W

County Pratt Total Depth 4480' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

415' of 8 5/8" surface pipe, cement circulated with 325 sacks. Fill hole with drilling mud to 350', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent