

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 20 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of Lauck Drilling Co. has this

date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Co. Inc.

Complete Address: 301 S. Broadway, Wichita, Kansas

Lease Name: Stelzer Well No. # 1

Location: C NE SW Sec. 7 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4910 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

311' of 8 5/8" surface pipe, cemented with 210 sacks.
Fill hole with drilling mud to 275', 1st cementing plug,
1/4 sack hulls, cement with 20 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, 1/4 sack hulls, cement with
10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent