

State of Kansas



15-055-30011-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Grandall of Shallow Water Refin. has this  
date requested permission to plug the following described well:

Mr. Grandall guarantees payment of the plugging fee.

Operator's full Name: Shallow Water Refining Company

Complete Address: 1325 Wichita Plaza, Wichita, Kansas

Lease Name: Jennings Well No. 1

Location: C NE NE Sec. 1 Twp. 22 Rge. 34 (E) (W)

County Finney Total Depth 4832' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Grandall was instructed to plug the well as follows:

8 5/8" to 428' circulated w/ cement. 5 1/2" to 4830' cemented.

Plug Back F.D. 4040' Top perforations 3994'

Plug bottom w/ sand & 5 sacks cement. Top of cement 3900'

Mud 3900' to 425' Rock Bridge & 35 sacks cement 425' to 325'

Mud 325' to 35' Plug, Huls & 10 sacks cement 35' to 0'

RECEIVED  
SEP 14 1967

Very truly yours,

E. J. Eves  
Conservation Division Agent  
Wichita, Kansas