

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 14 1963

10-14-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Troy Smith of Kent Well Servicing Co. has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kansas

Lease Name: Helmke "A" Well No. # 1

Location: SW SW SW Sec. 19 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4327 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Smith was instructed to plug the well as follows:

282' of 8 5/8" surface pipe, cemented to top. 4310' of 5 1/2"  
long string, cemented with 175 sacks. Sand to 4300', cement  
with 5 sacks. Fill hole with mud to 260', 10' rock bridge,  
cement with 25 sacks. Fill hole with mud to 40', 10' rock  
bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent