

State of Kansas



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date October 4, 1958, authorized the following plugging operation:

Operator's Full Name: Beardmore Drilling Co.

Complete Address: 827 Beacon Bldg., Wichita, Kans.

Lease Name: Siedel Well No. 4

Location: SW SE NW Sec. 19 Twp. 27 Rge. 12 (E) (W) X

County: Pratt Total Depth: 4341

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Top perf 4309. 346' of 8 5/8" surface casing circulated with cement.
Sand hole to 4300' and dump 5 sack cement on bottom. After pulling
pipe fill hole to 350' with heavy mud. Place rock bridge from 350'
Place 20 sack cement from 340'. Heavy mud to 40'. Place rock bridge
from 40' with cement from from rock bridge to base of cellar.

Very truly yours,

Signed: _____

Conservation Division Agent

RECEIVED
 STATE CORPORATION COMMISSION

OCT 22 1958

CONSERVATION DIVISION
 Wichita, Kansas