

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bigheart of Abercrombie Drlg Co has this

date requested permission to plug the following described well:

Mr. Bigheart guarantees payment of the plugging fee.Operator's full Name: Abercrombie Drlg IncComplete Address: 801 Union Center Wichita, KSLease Name: Livengood Well No. 1Location: N/2 N/2 NW Sec. 23 Twp. 27s Rge. 18 (E)(W) WCounty: Kiowa Total Depth 4790 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Bigheart was instructed to plug the well as follows:440 ft 8 5/8 surface cemented with 325 sacks. Lost bit &surface pipe in hole. Pump plug to 500 ft with 150 sackscement. 2nd plug at 325 ft with 100 sacks. 3rd plug at180 ft with 50 sacks. Mud to 40 ft, plug, 1/2 sack hulls,20 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent