

10 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name D. R. Lauck Oil Co. Inc.

Complete Address: 301 S. Broadway, Wichita, Kansas

Lease Name Stelzer Well No. # 1

Location C NE SW Sec. 7 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4910

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Lauck Drilling Co.

Address: 301 S. Broadway, Wichita, Kansas License No.     

Operation Completed: Hour 8:00AM Day 17th Month Sept. Year 1963

The Above well was plugged as follows:

311' of 8 5/8" surface pipe, cemented with 210 sacks. Hole was filled  
with drilling mud to 275', 1st cementing plug was bridged with 1/2 sack  
hulls at 275', cemented with 20 sacks. Hole was filled with drilling  
mud to 40', 2nd cementing plug and 1/4 sack hulls was bridged at 40',  
cemented with 10 sacks to base cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 9/20/63  
INV. NO. 7790-W

Signed: Archie Elving  
Well Plugging Supervisor