

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. -6015 6-15 County: Pratt

Location: NW NW SE Sec. 26 Twp. 29 Rge. 13 (E) (W) x

Name of Field: _____ Total Depth: 4710

I have this date completed supervision of plugging of:

Lease Name: Combs Well No. 1

Operator's Full Name: The Texas Company

Complete Address: 614 Bitting Bldg., Wichita, Kans.

Plugging Contractor: Wilson Inc.

Address: Stafford, Kans. License No. 375

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No x

If yes how long? _____ Reason: _____

Operation Completed: Hour 12AM Day 14 Month Jan. Year 1959

The above well was plugged as follows:

377' of 103/4" surface casing circulated with cement. Top Perf. 4608'. Hole was sanded
to 4602 with 5 sack cement dumped with dump bailer. Hole was filled to 350 with heavy
md. A rock bridge set from 350 to 340' and 20 sack cement dumped top bridge. Heavy
md to 40'. Rock bridge set at 40' to 30' and 10 sack cement placed to base of cellar.

Signed: _____
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 26 T. 29 R. 13W
BOOK PAGE 6 LINE 15

RECEIVED
COMMISSION
JAN 17 1959
CONSERVATION DIVISION
Wichita, Kansas