

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 05 1978
4-5-78
(of this well)
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - -

Operator's Full Name White Hawk Oil Co.
Complete Address Box 1150, Ely Bend, Kans. 67530
Lease Name Tarrison Well No. 4
Location NW-NW-SW- Sec 26 Twp 29^S Rge. 13 (E) (W) X
County Pratt Total Depth 4625
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____

Plugging Contractor Lockhold Engineering, Inc.
Address Box 698, Ely Bend, Kans. 67530 License No. 670
Operation Completed: Hour 11:30 Am. Day 31 Month March Year 1978

The above well was plugged as follows:

920' - 8 7/8" Casing w/ 450 sack Cement - 5 1/2" Casing set @
4574' w/ 165 sack Cement. Prof. 4605' - Sand back to 4540'
mix & dump 5 sack Cement on top of sand w/ dump bails
Pull 3300' - 5 1/2" Casing - set rock bridge from 400'
back to 375' dump 6 yard ready mix Cement to
top of Casing -
Pratt Ready Mix Cement - Pratt, Kans. 67124

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-5-78
INV. NO. 7058-a